



January 2, 2015

**150 MPH Wind Rider
Direct Membrane Termination Structural Concrete Deck**

1. 2001 Co. agrees to offer a 150 mph Wind Rider for a Direct-to-Deck termination with 2001 Co.

term bar fastened 7” on center using concrete fasteners into the structural concrete deck on an 18 gauge metal pan. The concrete fastener must have a minimum pull-out of 800 pounds.

2. Note: This **Direct Membrane Termination Air Seal** must be two or more feet in, away from the perimeter edge to act as a peel stop as well the main termination for the field membrane.

Note: T-Bar terminations of roof membrane parallel to the perimeter edge of a concrete deck can cause a fracture of a concrete deck from the pre-drilled holes.

3. MUST use approved 2001 Co. details for the installation of this roof system.